

99-5-ROAD
LAWRENCE TWP T-990 High Level Rd

Clearfield COUNTY

RESOLUTION NO. 97-3

WHEREAS, the Department of Transportation and this Municipality have agreed to transfer from state to municipal control the portion of

SR 1020 From segment 10 offset 0000
(state route) To segment 10 offset 2754

A distance of 0.5193 miles, in accordance with 75 Pa C.S., Chapter 92 and subject to completion by the Department of the rehabilitative work enumerated on the attached Form M-4226, which the Department and the municipality agree would put the highway in acceptable condition, and

Additional Mileage Information:

LR 17134 from station 22+60 to station 51+00
A distance of 2742 feet or 0.5193 miles.

Actual field measured footage: 2736 (in feet).

Actual field measured mileage: 0.5182 (in miles). Signature: *Ray A. Prothman*

WHEREAS, the Department and the municipality have agreed that annual maintenance payments under 67 Pa C.S., Section 9511(g) shall be paid to the municipality, beginning April 1, 2000, the approximate amount of payment will be based on the \$2,500 per lineal mile payable under the provisions of the Department's Transfer Program.

NOW THEREFORE, it is resolved by the Lawrence Township Board of Supervisors
(name of governing body)
that *Donald M. Kelly* is authorized to execute this agreement on behalf of the municipality.
(name of authorized officer)

The effective date of transfer of the above portion of highway shall be on or before 12-31-98.

ATTEST: *George W. Anderson* Lawrence Township
Secretary (name of municipality)
BY: *Donald M. Kelly*
Chairman

I certify that the foregoing is a true and correct copy of the Resolution adopted at a meeting of the
Lawrence Township Board of Supervisors
(name of governing body)

Held on: May 20, 1997
Date: May 20, 1997

George W. Anderson
Secretary

REMARKS: Bridge and approach area from Segment 10/Offset 0110 to Segment 10/Offset 0122 will be retained by the Pennsylvania Department of Transportation.

Source documentation for cost estimation: BID ANALYSIS MANAGEMENT SYSTEM

FILED

FEB 05 1997

William A. Shaw
Prothonotary



Route S.R. 1020 Clearfield County Lawrence Township XXX
XXX
XXX
 Segment/Offset 10/0000 To Segment/Offset 10/2754 2742 feet = 0.5193 miles
 Type of Pavement Bituminous Width of Paved or Graded Section 19'
 Condition at time of Inspection _____ May 8 19 97
 Right of Way 33 feet & variable

Surface - Need resurfaced.
 Shoulders - Add material.
 Drainage - Replace pipes.
 Bridges - From segment 10/ offset 0110 to segment 10/ offset 0122 will be retained by PennD.O.T.
 Miscellaneous - Cut trees and tree limbs.

Number of Department Owned Signs to be Removed - All signs on the entire route will remain in place except for the S.R. signs, will be removed prior to transfer of route.

Work required to place road in Acceptable Condition

- The Pennsylvania Department of Transportation will do the improvements in order to put the route into an acceptable condition.

- | | |
|---|--------------|
| 1. Widen existing roadway to obtain a 24 foot roadway with 4" of Bituminous Concrete Base Coarse, approximately 403 Tons of BCBC @ \$30.00/Ton. | \$ 12,090.00 |
| 2. Bituminous Wearing Coarse (approximately 1 1/2" depth), on the entire route, approximately 606 Tons @ \$32.00/Ton. | \$ 19,392.00 |
| 3. Add material to shoulders (1'- 2' left and right), approximately 134 Tons @ \$18.00/Ton. | \$ 2,412.00 |
| 4. Prime coat of stabilized shoulders (1'-2' left and right), approximately 274 gallons @ \$1.40/gallon. | \$ 383.60 |
| 5. Add delineator posts at all pipe locations. | \$ 300.00 |
| 6. Cutting and trimming of tree limbs and brush. | \$ 700.00 |
| 7. Review existing signing on the entire route to determine if any of them needs replaced or added. | \$ 2,000.00 |

NOTE: All Department Force work will be done by December 31, 1998.

It is agreed that the completion of the work listed above will place this road in Acceptable Condition

District Engineer

For Local Authorities

The work listed above has been completed and the road is in Acceptable Condition

Date



Route S.R. 1020 Clearfield County Lawrence Township Box
City
 Segment/Offset 10/0000 To Segment/Offset 10/2754 2742 feet = 0.5193 miles
 Type of Pavement Bituminous Width of Paved ~~WIDENED~~ Section 19'
 Condition at time of Inspection _____ May 8 19 97
 Right of Way 33 feet & variable

Surface - Need resurfaced.

Shoulders - Add material.

Drainage - Replace pipes.

Bridges - From segment 10/offset 0110 to segment 10/offset 0122 will be retained by PennDOT.

Miscellaneous - Cut trees and tree limbs.

Number of Department Owned Signs to be Removed - All signs on the entire route will remain in place except for the S.R. signs, will be removed prior to transfer of route.

Work required to place road in Acceptable Condition

- The Pennsylvania Department of Transportation will do the improvements in order to put the route into an acceptable condition.

- | | |
|---|-------------|
| 8. Correct driveway approaches either by adding stabilization material or amiesite. | \$ 99.48 |
| 9. Painting of double yellow centerline on the entire route, 2754 LF @ 2 Lines @ 0.12/LF. | \$ 660.96 |
| 10. Painting of white edge line on the entire route, 2754 LF @ 2 Lines @ 0.12/LF. | \$ 660.96 |
| 11. Flushing of pipes at various locations. | \$ 2,300.00 |
| 12. Cleaning of parallel ditches and all pipe outlet ditches on entire route. | \$ 2,500.00 |
| 13. Replace 3 existing cross pipes with approximately 110 feet of 18" corrugated plastic pipe with smooth liner (2locations) and 66 feet of 36" corrugated metal pipe @ 25.00/LF. | \$ 4,400.00 |
| 14. Add approximately 700 feet of used 2-S Strong Post guide rail from segment 10/offset 1000 to segment 10/offset 1700, left side, @ \$5.00/LF. | \$ 3,500.00 |

NOTE: All Department Force work will be done by December 31, 1998.

It is agreed that the completion of the work listed above will place this road in Acceptable Condition

District Engineer

For Local Authorities

The work listed above has been completed and the road is in Acceptable Condition

Date



Route S.R. 1020 Clearfield County Lawrence Township Box
City
 Segment/Offset 10/0000 To Segment/Offset 10/2754 2742 feet = 0.5193 miles
 Type of Pavement Bituminous Width of Paved ~~Un~~Graded Section 19'
 Condition at time of Inspection _____ May 8 19 97
 Right of Way 33 feet & variable

Surface - Need resurfaced.
 Shoulders - Add material.
 Drainage - Replace pipes.
 Bridges - From segment 10/offset 0110 to segment 10/offset 0122 will be retained by PennD.O.T.
 Miscellaneous - Cut trees and tree limbs.

Number of Department Owned Signs to be Removed - All signs on the entire route will remain in place except for the S.R. signs, will be removed prior to transfer of route.

Work required to place road in Acceptable Condition

- The Pennsylvania Department of Transportation will do the improvements in order to put the route into acceptable condition.

15.	Add inlets, <u>5</u> inlets @ 1250 each.	\$ 6,250.00
16.	Realigning the S.R. 1020/1001 intersection by adding either one or two lanes to improve the traffic flow and safety at the intersection.	\$ 9,700.00
17.	Relocate one utility pole near the S.R. 1020/1001 intersection.	\$ 1,351.00
18.	Removal of S.R. signs on the entire route.	\$ 300.00
Total		\$ 69,000.00

NOTE: All Department Force work will be done by December 31, 1998.

it is agreed that the completion of the work listed above will place this road in Acceptable Condition

District Engineer

For Local Authorities

The work listed above has been completed and the road is in Acceptable Condition

Date

Condition of Pipes on S.R. 1020 in Lawrence Township beginning at the Intersection of S.R. 1006 and proceeding to the Intersection of S.R. 1001.

- | | | |
|----|------------------------|--|
| 1. | Segment 10/Offset 0360 | - 18" Corrugated Metal Pipe needs flushed. |
| 2. | Segment 10/Offset 0584 | - 18" Corrugated Metal Pipe needs flushed, add inlet left side. |
| 3. | Segment 10/Offset 0655 | - 24" Concrete Pipe needs flushed. |
| 4. | Segment 10/Offset 1144 | - 18" Concrete Pipe needs flushed. Add inlet, left side. |
| 5. | Segment 10/Offset 1470 | - 18" Concrete Pipe needs flushed. |
| 6. | Segment 10/Offset 1768 | - 18" Concrete Pipe needs flushed. |
| 7. | Segment 10/Offset 2067 | - Replace existing cross pipe with 50' of 18" corrugated plastic pipe with smooth liner, add inlet, left side. |
| 8. | Segment 10/Offset 2559 | - Replace existing cross pipe with 66' of 36" corrugated plastic pipe with smooth liner, add inlet, left side. |
| 9. | Segment 10/Offset 2658 | - Replace existing cross pipe with 60 feet of 18" corrugated plastic pipe with smooth liner, add inlet, left side. |

Install delineator posts at all pipe locations, clean all outlet ditches.

FILED

Rec'd
\$20

FEB 05 1999

0/11:32

William A. Shaw

Prothonotary

Cheryl D. Shaw